Sl	Item Code	Item Name	Unit	Quantity	Approved Estimate Price (INR)	Unit Rate(All Inclusive)	Amount	Amount In Words	Action
11	12	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete. d) 100 Amps	Each	65	415	300	19500	Ninteen Thousand Five Hundred (dot) Zero	
12	12	Supplying and fixing Microprocessor based Astronomical timer switch with using necessary bolts, nuts and washers etc.,	Each	65	7515	7000	455000	Four Lakh Fifty Five Thousand (dot) Zero	
13	12	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required. a) 5-32 Amps SP 1) Group 'A'	Each	65	195	100	6500	Six Thousand Five Hundred (dot) Zero Only.	
14	12	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947. d) 100-125 Amps	Each	65	7450	7000	455000	Four Lakh Fifty Five Thousand (dot) Zero	
15	12	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. . (32.9a)	Rmtr	130	240	100	13000	Thirteen Thousand (dot) Zero Only.	
16	12	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes	Each	260	14	5	1300	One Thousand Three Hundred (dot) Zero Only.	
17	12	Supplying.....amps rated 3 phase with neutral bus bar using requirement capacity electrolytic aluminium strips covered with heat shrinkable coloured PVC sleeve, mounted on phenolic/FRP/DMC insulator which are mounted on powder coated 40x6 mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. 100Amps 4x30x6mm Alluminium Strips	Rmtr	13	1600	1000	13000	Thirteen Thousand (dot) Zero Only.	
18	12	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV Class 4 core 16sqmm	Per Mtr	650	150	100	65000	Sixty Five Thousand (dot) Zero Only.	
19	12	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required. I. In existing trench /duct.a. 6 sqmm to 16sqmm	Rmtr	650	8	5	3250	Three Thousand Two Hundred and Fifty (dot)	

Total Bid Amount

Total Bid Amount (Rs. in figures) : 2200875

Total Bid Amount (Rs. in words) : Twenty Two Lakh Eight Hundred and Seventy Five (dot) Zero Only.

Back

This site is best viewed in 1024x768 resolution.

Thursday, 24 July 2014 11:32:18

DashBoard Blue English Logout

Welcome K NAGESH (I/C)

My Profile Indent Management Tender Management Catalogue Management Payment Reports Contract Management Auction Management

Commercial Bid Item Details

Tender Details

Tender No. : BBMP/2013-14 /EL/WORK_INDENT7970/CALL-3

Tender Title : Providing sodium vapour street light fittings , control switches and control wires at various ward in Dasarahalli zone.

Department : Bruhat Bengaluru Mahanagara Palike

Sl No	Item Code	Item Name	Unit	Quantity	Approved Estimate Price (INR)	Unit Rate(All Inclusive)	Amount	Amount In Words	Action
1	12	Supplying High Pressure Sodium vapour street light fitting die Cast aluminium Canopy With aluminum housing for control gear, finished stove enamel gray glassy white canopy interior with a pair of anodized aluminum reflectors with toughened flat glass, gasket lining for drip inseat resistance duly wired with porcelain holder copper choke, igniter and HPF condenser including a sodium vapour lamp. I) 250 Watts a)Group'A' Make :Philips, Wipro, Hevells, Bajaj, Surya,CG,Schreder,Hallonix	Each	150	6150	6100	915000	Nine Lakh Fifteen Thousand (dot) Zero	
2	12	Supplying & fixing of.....mm dia class A G1 pipe bracket upto 2 mtrs long bent at suitable angle and fixing to this btacket 1*40/2*40 Watts fluorescent tube street light fitting of all capacities to G1 or C1 or rail or RCC pole/Wall using suitable clamps,bolts, and nuts and wiring using suitable capacity wires complete a)using 32mm dia G1.pipe	Each	150	685	600	90000	Ninty Thousand (dot) Zero Only.	
3	12	Supply and erection of .....mtr RCC pole including earth work etc., complete as per the standard technical specification.	Each	5	6583	3000	15000	Fifteen Thousand (dot) Zero Only.	
4	12	Supply and fixing of ..... cross arm including all Hardwares compete as per the standard technical specification. b) 2 Pin 45x45x5mm-510mm	Each	150	123	50	7500	Seven Thousand Five Hundred (dot) Zero	
5	12	a) 4 Pin 45x45x5mm-1110mm	Each	5	229	100	500	Five Hundred (dot) Zero Only.	
6	12	Supplying and Fixing..... including all Hardwares etc complete as per the Standard technical Specification.	Each	160	70	30	4800	Four Thousand Eight Hundred (dot) Zero	
7	12	d) No.8 Strain Insulator	Each	15	24	10	150	One Hundred and Fifty (dot) Zero Only.	
8	12	Supplying and stringing of ACSR Conductor (6/2.59mm Al+1/2.59mm steel)	Mtr	3500	19.8	10	35000	Thirty Five Thousand (dot) Zero Only.	
9	12	Supplying and fixing ..... including all Hardwares etc complete as per the standard technical specification	Each	155	61	25	3875	Three Thousand Eight Hundred and Seventy Five	
10	12	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete b) 16 SWG	SqCm	487500	0.33	0.2	97500	Ninty Seven Thousand Five Hundred (dot) Zero	